

KALPVRIKSHA DESIGN'S

Engineer – Architect – Consultant- Designer

AREA STATEMENT AS PER**CLIENT'S/APPLICANT'S CONSENT****DATE:03/07/26**

TOTAL PLOT AREA :- 800 SQ.FT.

GROUND FLOOR COVD. AREA :- 800 SQ.FT.

FIRST FLOOR COVD. AREA :- 00 SQ.FT.

SECOND FLOOR COVD. AREA :- 00 SQ.FT.

TOTAL COVD. AREA :- 800 SQ.FT.

GRUND COVERAGE IN %:100

Estimate for proposed construction work on GROUND FLOOR FOR MR.DEEPAK KUMAR S/O.KAUSHAL KISHORE,ADD.-PLOT PART OF GATA NO.-220,SITUATED AT-RAJSAW GRAM.- PALTUPUR,PARGANA AND TEHSIL-GHATAMPUR,AND DISTRICT-KANPUR NAGAR					
S.N.	Description	TOTAL COVERED AREA(SQ.MT)			74.34
		Unit	Quantity	Rate	Amount
1	Earth work in excavation in trenches for foundations in ordinary soil (loam clay or sand) including lift upto 1.5 mt. and lead up to 50 mt., dressing of sides and ramming of bottoms and disposal of excavated earth as directed by E.I.C.	Cum	40.00	50.00	2000.00
2	Providing and laying cement concrete 1:5:10 (1 Cement, 5 fine sand 10 brick aggregate graded 40 mm. nominal size) in foundations and under floors, including cost of formwork, ramming of layers and curing complete in all respects.	Cum	33.36	1450.00	48371.26
3	Class 150 brick work in 1:4 (1 cement 4 fine sand of 1.25 fineness modulus) mortar in foundations and up to plinth level including supply of all materials, labour tools and plants for proper completion of work including curing of brick work complete in all respects.	Cum	45.27	2200.00	99601.90
4	Providing and laying damp proof course 25 mm. thick 1:2:4 (1 cement, 2 course sand, 4 graded stone aggregate 10 mm. nominal size) including supply and mixing of damp proof compound as per ISI specifications complete in all respects.	Sqm	52.42	220.00	11532.85
5	Class 150 brick work as in item no. 3 but in superstructure in 345 / 230 mm. walls including necessary cutting and moulding of brick, curing of brickwork and including supply of all materials tools and plants for proper completion of work.	Cum	38.13	3200.00	122000.41

KALPVRIKSHA DESIGN'S

Engineer – Architect – Consultant- Designer

6	Reinforced brick work in slabs, sunshades etc. with 150 class bricks laid in 1:3 cement coarse sand mortar excluding supply of reinforcement and its bending binding and laying, but including all centering shuttering, curing and supply of all materials tools and plants for proper completion of work.	Cum	2.00	6600.00	13200.00
7	R.C.C. in roof slab, lintels etc. with cement, approved coarse sand and 2 cm. gauge approved stone ballast in the proportion 1:2:4 excluding supply of inforcement.	Cum	2.00	7000.00	14000.00
8	Mild steel work in reinforcement for RCC or RB work including bending, placing and binding of bars as per drawing and as directed including cost of binding wire and overlaps and wastage complete in all respects.	Kg.	33.00	65.00	2145.00
9	Supplying fabricating and fixing wooden door and window frames with proper joinery bonded with approved quality glue. The frames shall be sand papered for proper finish as directed by E.I.C. The wood shall be of best quality properly seasoned, free of knots and warping.	Cum	1.00	38000.00	38000.00
10	Supplying all materials fabricating and fixing steel grills or staircase railings as per design.	Kg.	142.97	250.00	35742.31
11	15 mm Cement plaster in single coat on the fair and rough side of single or half brick wall for interior internal rounded angles	Sqm	297.85	350.00	104248.40
12	As in items 11 but for plastering on ceiling and soffit of stair.	Sqm	83.03	450.00	37363.22
13	C/C CONCRETE flooring	Sqm	83.03	1690.00	140319.65
14	P/L Kota Stone in staircase	Sqm	26.21	650.00	17037.17
15	Painting first coat over priming coat including cost of priming coat on steel and other metal surfaces area with superior synthetic enamel such as including cleaning the surface of all dirt and dust and other foreign materials and papering.	Sqm	22.00	250.00	5500.00
16	Supplying fabricating and fixing 32 mm. thick flush doors as per I.S. specifications of approved quality including 12 mm. T/W lipping fixed with glue and headless nails and including fixing and adjustment of hinges locks, bolts, handles and other fittings	Sqm	19.81	2850.00	56467.48
17	P/L Kota Stone in open area	Sqm	0.00	575.00	0.00

KALPVRIKSHA DESIGN'S

Engineer – Architect – Consultant- Designer

1 8	Sand filling	Cum	0.00	600.00	0.00
1 9	Roof terracing	Cum	0.00	1500.00	0.00
2 0	Wood work in cupboard	Sqm	9.00	8500.00	76500.00
2 1	P/L textured finish on wall surface	Sqm	12.00	1200.00	14400.00
2 2	Providing septic tank & soak pit	No.	0.00	40000.00	0.00
2 3	P/L Kajaria tiles on Wall surface	Sqm	3.00	1250.00	3750.00
2 4	P/L granite kitchen-otta	No.	1.00	12000.00	12000.00
2 5	Water proofing treatment	Sqm	13.11	675.00	8846.22
2 6	P/F of Main Gate (M.S.)	No.	1.00	29000.00	29000.00
2 7	Providing anti-termite treatment	Sqm	13.00	350.00	4550.00
2 8	Dismantling of Plaster	Sqm	0.00	15.00	0.00
2 9	Dismantling of Brick Work	Cum	0.00	200.00	0.00
Total					896575.87
Adding 8% for electrical work					71726.07
Adding 8% for Sanitary work					71726.07
Net Total					1040028.01
Estimate for proposed construction work Covered Area 74.34 Sqmt. (800.00 Sq Ft @1300 per Sqft)					
Say					1,040,000.00
(Rs.TEN LAKHS AND FOURTY THOUSAND ONLY)					

Kalpvriksha Design's
Er. Shubham Upadhyay
 Regd. AM3121561
 Mob: 7068500996